

BEML LIMITED, BANGALORE COMPLEX

Ref:RMM/TEN- 6300027932/2019

Date: 04.06.2019

ISSUED TO:	Period of contract:	02 Months
	EMD :	13200.00

Sub:Providing Vitrified tile Flooring for Ground Floor of CQA Office Building in BEML Ltd, Bangalore Complex, Bangalore

SCHEDULE 'A' - BILL OF QUANTITIES

Sl. No	Description	Unit	Qty	Rate/unit in fig. & in words Rs.	Amount (Rs)
1	Dismantling the existing old mosaic flooring & skirting tiles including cement mortar bedding but not backing coat and removing debris from the premises etc., complete all as specified and directed by Engineer-in-charge. Note: The dismantled materials should be removed immediately from the premises without disturbing the regular office atmosphere	Sqm	300		
2	Providing and laying in Position Plain Cement screed Concrete of mix proportion 1:2:4 in floors and other similar works of average thickness 20mm thick using 12.5mm down graded granite aggregate, laid in layers and well compacted,mechanical/manual mixing laid to required thickness & gradient as per site condition and finishing the surface smooth & even including curing etc.,complete all as specified and directed by Engineer in charge.	Cum	7		
3	Providing & laying bedding layer of 20mm thickness in Cement Mortar 1:6 in floor & skirtings, finished smooth & even to required gradient etc., complete all as specified and directed by Engineer in charge.	Sqm	300		
4	Providing & laying 10mm thick vitrified tiles (square / rectangular shape) manufactured by M/s. Naveen/ Johnson/ Kajaria/Somany/RAK in floor & skirtings (6" ht), set and jointed in neat cement slurry and pointed with white cement & matching coloured pigment to match with the existing shade of selected tiles etc., complete all as specified & directed. Note: (1) Skirting tiles will be measured and paid in this item on area basis only and no separate measurement (in RFT/RMT) will be allowed (2) The quoted rate is deemed to include for all wastages.(3) The basic cost of tiles shall not be less than Rs.75/Sqft inclusive of GST & contractor has to produce documentary evidence/invoice for the same for settlement of bills	Sqm	300		
5	Carting away unusable broken/dismantled tiles, cement/concrete debris outside the site premises to a distance not exceeding 5.0KM and dumping at a location in BEML Township area including all lead and lift etc., complete all as specified and as directed by Engineer in charge.	Cum	20		
Note:					
(1) Interested bidders/contractors are requested to visit the site and acquaint themselves with the site conditions before submission of their quote/offer for the work					
(2) The bidders/contractors may note that on placement of PO for the work, the colour/shade/design of vitrified tiles will be selected by BEML from the mentioned brands/manufacturers and contractor has to produce shade card of the manufacturer including tile samples for selection by BEML.					
	Total value of work excluding GST			Rs.	
	GST		%	Rs.	
	Total value of work inclusive of GST			Rs.	

Total Amount in words Rupees_____

Authorised Signatory
(Purchase Dept)

Signature of the Contractor
with seal