

BEML LIMITED, BANGALORE COMPLEX

Ref : 6300035697

Date: 16.03.2021

ISSUED TO:	Period of contract:	45 days
	EMD :	Rs. 4,805.00

Sub:Providing laminated wooden flooring at Director (R&M) and Executive Director (R&M) chambers at Bangalore Complex, BEML Ltd, Bangalore 75.

SCHEDULE 'A' - BILL OF QUANTITIES

Sl. No	Description	Unit	Qty	Rate/unit in fig. & in words Rs.	Amount (Rs)
1	Modification to the existing wooden door shutters by the following: a) Removing the existing door shutter of size approximately (1.20mtrx2.10mtr) carefully without damaging and stacking at a place as shown by BEML. b) Modifying the height of door by cutting the door shutter to the required size c) Refixing back the door in the same location using necessary hardware items viz., screws, nails, hinges, locking arrangement etc.,complete all as specified and directed by engineer in charge.	Each	4		
2	Removing the existing PVC flooring /carpet etc., including any backing coat and handing over to BEML Ltd and providing and installation of new laminated wooden flooring of product code: LCF 050/LCF014 AC4 grade, LOC Series not less than 7mm thick, 32 Class, manufactured by M/s. Pergo/Trysquare/ Square foot or equivalent of approved shade / design / colour with backing layer of 3mm thick thermofoam sheet including necessary end profile, edge beading skirting of required width as per site conditions, including all necessary hardware items etc., complete all as per manufacturers instructions and as specified & directed by engineer in charge. Note: The rate quoted is deemed to include for a) preparation of the existing floor surface by removing all dust, dirt and making it dry, clean and perfectly level before laying of the laminated wooden flooring. b) The rate is include for all wastages.	Sqm	110		
3	Preparing the existing old painted wooden surface by scrapping, cleaning & applying two or more coats of french sprit polishing with wood filler of matching color pigment/powder, manufactured by M/s.Asian paints / M/s. Berger Paints etc., complete all as specified and directed by engineer in charge.	Sqm	14		
	Note:				
	(1) Interested bidders/contractors are requested to visit the site and acquaint themselves with the site conditions before submission of their quote/offer for the work.				
	(2) The rate quoted by the bidders/contractors is deemed to include for providing & removal of scaffolding/staging as required for the work under the relevant item.				
	Total value of work excluding GST			Rs.	
	GST			Rs.	
	Total value of work inclusive of GST			Rs.	

Total Amount in words Rupees_____

Signature of the Contractor
with seal