

Bid invitation

Information

Description: EMCP/Compound walls-KGF/

Bid invitation number: 6300037859

Version: 1

Bid invitation rules

Bid invitation currency: INR

Timezone: INDIA

Submission period: 26.08.2022 16:00:00

Tech Opening date: 26.08.2022 16:00:00

Created On: 12.08.2022 08:34:09

Bid invitation text:

Sub : Re-construction of collapsed perimeter compound walls at Tower-1 at HFU, Tower-1 at EM Division, Tower-4 at EM Division & Officers Quarters, BEML Ltd., KGF.

Tender Documents uploaded as attachments to the Bid Invitation 6300037859.

Bidders are requested to attach only Documents towards Technical Qualifying Criteria / Pre-Qualification Details / Scanned copies of EMD paid / exemption details in the Collaboration Folder and submit the commercial details in Item Data only. Any item specific remarks / comments can be mentioned in "Bidders Remarks" column under ItemData.

Please contact BEML SRM Team for getting user ID & password / clarification during the submission of bid through SRM / guidance on submission of bids in SRM system.

Phone : (080) 22963269 / 22963141

e-mail ID : admin.srm@beml.co.in

Please contact Contract Purchase, EM Division, BEML, KGF for any clarifications on the Tender Documents.

Phone : (08153) 279365

e-mail ID : emekgf@beml.co.in

Note :

1. This is a requirement of BEML Limited, Kolar Gold Fields - 563 115.

Bid invitation

Information

Description: EMCP/Compound walls-KGF/

Bid invitation number: 6300037859

Version: 1

2. Firms are requested to submit their bid.

3. Firms to quote UNIT RATES only (not extended value like unit rate x qty) against specific BOQ items and units as indicated in BOQ. Unit rates EXCLUDING GST are to be entered in the BEML SRM system, only in the 'Item Data'. Format given below is to be referred and the unit values are to be entered in the system against the respective item in the 'Item Data'.

4. In case of any doubt regarding submitting the quote, don't assume, please contact the concerned officer as indicated in the tender and quote correctly.

5. To get familiarise with the area of work the firm is advised to make a personal pre bid visit to BEML works, consult the concerned officer and get clarified. Ignorance of site conditions at later stage will not be entertained by BEML.

6. Bid should be for the complete scope of work specified (i.e. firm has to quote for all). Quoting for all BOQ items is mandatory.

7. Selection of L1 firm will be based on the value of Total value "Sum [(QTY x Unit Rate)]" for all items as per BOQ.

8. Payment Terms will be against certification of In-charge, Civil Maintenance Department, EM Division, BEML Ltd., KGF for Re-construction of compound walls at HFU & EMD and In-charge, Estate Maintenance, BEML Ltd., KGF for Re-construction of compound wall at Officers Quarters (SRM code = L046). Bidders are requested to indicate / select the same while quoting the commercial bid.

9. Please follow the instructions mentioned below for submitting Bid.

- a) Use Internet Explorer (IE 8 and above)
- b) Open BEML home page - <http://www.bemlindia.in>
- c) Click on Purchase > e-Procurement (SRM)
- d) After Logging in, you to see the Tenders available to you.
- e) Click on "Notes and attachments" to see the details of terms & Conditions and Specification of the Item.

10. Valid Class 3 Digital Signature and Encryption certificate is mandatory for submission of bids in SRM e-Procurement System.

11. Bidders are requested to indicate price break-up details, if any, in "Price conditions" of the "Items".

12. Bidders may indicate any additional details for the above requirement in the form of attachments in the "Notes and attachments".

13. Delivery Term : FDD, BEML Ltd., KGF. This is Service requirement.

14. Validity : Bid should be valid for 90 days from the date of closing date of tender.

15. Bidder to enclose applicable MSME, SC/ST Entrepreneur Certificate, etc. in the format available in collaboration folder.

Bid invitation

Information

Description:EMCP/Compound walls-KGF/

Bid invitation number:6300037859

Version: 1

16. The details of compound walls to be re-constructed are as follows :

A. Re-construction of Collapsed perimeter Compound wall near Tower -1 at HFU, BEML Ltd., KGF.

B. Re-construction of Collapsed perimeter Compound wall between Tower No.1 and tower No.2, at EM Division, BEML Ltd., KGF.

C. Re-construction of Collapsed perimeter Compound wall near Tower -4 at EMD, BEML Ltd., KGF.

D. Re-construction of collapsed compound wall Back side of C50 to C56 quarters near Vasanth Nagar, BEML Ltd., KGF.

17. Line item no. 1 to 24 shown in BOQ are for the requirements mentioned in above SI No. 16A/16B/16C & Line item no. 25 to 37 shown in BOQ are for the requirements mentioned in above SI No. 16D. Firms are requested to note this and quote accordingly.

Attachments:

TENDER DOCUMENT

CIVIL WORKS TERMS & CONDITIONS

NIT ACCEPTANCE LETTER

CHECK LIST

Digital Signature

Bid invitation details

Item	Product Price Condition	Description	Vendor product number	Delivery date/ performance period	Quantity
1		Earthwork Excavation in Trenches			98.000 M3

Item long text:

Construction of compound walls at Tower-1 at HFU/ Tower-1&2 at EM Division /Tower-4 at EM Division :
Earthwork Excavation in Trenches, not exceeding 1.5 m wide and not exceeding 1.5 m in depth; for foundation,
etc., and getting out,etc., complete.

Basic Price

INR

2		Providing & laying PCC 1:4:8			21.000 M3
---	--	---------------------------------	--	--	-----------

Item long text:

Construction of compound walls at Tower-1 at HFU/ Tower-1&2 at EM Division /Tower-4 at EM Division :
Providing & laying PCC 1:4:8, using 40mm graded granite aggregate, filling and mass concrete in foundation,
etc., complete.

Basic Price

INR

Bid invitation

Information

Description: EMCP/Compound walls-KGF/

Bid invitation number: 6300037859

Version: 1

Item	Product Price Condition	Description	Vendor product number	Delivery date/ performance period	Quantity
3		Supplying & constructing SSM walling			38.000 M3

Item long text:

Construction of compound walls at Tower-1 at HFU/ Tower-1&2 at EM Division /Tower-4 at EM Division :
Supplying & constructing Size Stone Masonry walling of squared rubble, regular coursed well bonded, bedded
and solidly hearted built in CM 1:6 in foundation, etc., complete. (Tower-1 & Tower-4).

Basic Price INR

4		Supplying & constructing SSM in block			18.000 M3
---	--	--	--	--	-----------

Item long text:

Construction of compound walls at Tower-1 at HFU/ Tower-1&2 at EM Division /Tower-4 at EM Division :
Supplying & constructing Size Stone Masonry in block in course masonry well bonded built in CM 1:6 in
foundation, etc., complete. (HFU).

Basic Price INR

5		Constructing Size Stone Masonry			20.000 M3
---	--	------------------------------------	--	--	-----------

Item long text:

Construction of compound walls at Tower-1 at HFU/ Tower-1&2 at EM Division /Tower-4 at EM Division :
Constructing Size Stone Masonry in walling of squared rubble, regular coursed well bonded, bedded & solidly
hearted built in CM 1:6 in walls with available stones, etc., complete (Tower -1).

Basic Price INR

6		Constructing Size Stone Masonry in block			30.000 M3
---	--	---	--	--	-----------

Item long text:

Construction of compound walls at Tower-1 at HFU/ Tower-1&2 at EM Division /Tower-4 at EM Division :
Constructing Size Stone Masonry in block in course masonry well bonded built in cm 1:6 in walls with available
stones, etc., complete (HFU).

Basic Price INR

7		Supplying&constructing Size stone Masonr			30.000 M3
---	--	---	--	--	-----------

Item long text:

Construction of compound walls at Tower-1 at HFU/ Tower-1&2 at EM Division /Tower-4 at EM Division :
Supplying & constructing Size Stone Masonry of squared rubble masonry, regular coursed, well bonded, bedded
and solidly hearted, built in CM 1:6, brought up to courses on walls, etc., complete.

Basic Price INR

8		Providing & laying PCC			5.000 M3
---	--	------------------------	--	--	----------

Bid invitation

Information

Description: EMCP/Compound walls-KGF/

Bid invitation number: 6300037859

Version: 1

Item	Product Price Condition	Description	Vendor product number	Delivery date/ performance period	Quantity
		1:2:4			
Item long text:					
Construction of compound walls at Tower-1 at HFU/ Tower-1&2 at EM Division /Tower-4 at EM Division : Providing & laying PCC 1:2:4 using 20mm graded granite aggregate, for plinth course, cills, strings, courses, copings, etc., complete.					
	Basic Price		INR		
9		Providing & construction of BBM			49.000 M3
Item long text:					
Construction of compound walls at Tower-1 at HFU/ Tower-1&2 at EM Division /Tower-4 at EM Division : Providing & construction of Burnt Brick Masonry of 'A Class bricks, built in cm 1:6 for superstructure, etc., complete.					
	Basic Price		INR		
10		Providing & laying PCC 1:2:4			2.000 M3
Item long text:					
Construction of compound walls at Tower-1 at HFU/ Tower-1&2 at EM Division /Tower-4 at EM Division : Providing & laying PCC 1:2:4 Concrete using 20mm graded granite aggregate for grouting angles, etc., complete.					
	Basic Price		INR		
11		Erecting & fixing Structural steel			1,200.000 KG
Item long text:					
Construction of compound walls at Tower-1 at HFU/ Tower-1&2 at EM Division /Tower-4 at EM Division : Erecting & fixing Structural steel works 'Y' angle for fencing post, etc., complete.					
	Basic Price		INR		
12		Providing & fabricating TMT steel bars			2,010.000 KG
Item long text:					
Construction of compound walls at Tower-1 at HFU/ Tower-1&2 at EM Division /Tower-4 at EM Division : Providing & fabricating TMT steel bars of 10mm dia. and over, cut to length, bent to shape required including cranking, bending spirally for hooping for columns, beams, hooking ends with and including mild steel wire (annealed) not less than 0.9mm dia. reinforcement for concrete, etc., complete.					
	Basic Price		INR		
13		Providing Form work to concrete surfaces			109.000 M2

Bid invitation

Information

Description: EMCP/Compound walls-KGF/

Bid invitation number: 6300037859

Version: 1

Item	Product Price Condition	Description	Vendor product number	Delivery date/ performance period	Quantity
Item long text:					
Construction of compound walls at Tower-1 at HFU/ Tower-1&2 at EM Division /Tower-4 at EM Division : Providing Form work to concrete surfaces in foundations, footings, bases of columns, beams, sides of soffits (if any) of foundation and plinth beams and similar work, etc., complete.					
	Basic Price		INR		
14		Supplying& fixing Galvanised wire			600.000 M
Item long text:					
Construction of compound walls at Tower-1 at HFU/ Tower-1&2 at EM Division /Tower-4 at EM Division : Supplying& fixing Galvanized 2 strand, steel Barbed wire 2.24 mm dia. barbs at 75mm spacing and straining and fixing to any type of standards rails straining bolts, including securing or tying at crossing with and provision of galvanized mild steel wire, as directed, etc., complete.					
	Basic Price		INR		
15		Rendering 10mm thick in CM 1: 6			420.000 M2
Item long text:					
Construction of compound walls at Tower-1 at HFU/ Tower-1&2 at EM Division /Tower-4 at EM Division : Rendering 10mm thick in CM 1: 6 on fair faces of brick or concrete surfaces, rendering to be finished even & smooth (without using extra cement), etc., complete.					
	Basic Price		INR		
16		Keyed Pointing in CM 1:4			412.000 M2
Item long text:					
Construction of compound walls at Tower-1 at HFU/ Tower-1&2 at EM Division /Tower-4 at EM Division : Keyed Pointing in CM 1:4, to squared rubble masonry, concrete, or uncoursed or brought up to courses, etc., complete.					
	Basic Price		INR		
17		Preparing the wall surfaces			250.000 M2
Item long text:					
Construction of compound walls at Tower-1 at HFU/ Tower-1&2 at EM Division /Tower-4 at EM Division : Preparing the wall surfaces and applying two coats Cement paint <u>over a coat of primer</u> , etc., complete.					
	Basic Price		INR		
18		Preparing the steel surfaces			16.000 M2
Item long text:					
Construction of compound walls at Tower-1 at HFU/ Tower-1&2 at EM Division /Tower-4 at EM Division : Preparing the steel surfaces and applying two coats enamel paint over a coat of primer, etc., complete.					

Bid invitation

Information

Description:EMCP/Compound walls-KGF/

Bid invitation number:6300037859

Version: 1

Item	Product Price Condition	Description	Vendor product number	Delivery date/ performance period	Quantity
	Basic Price		INR		
19		Returning, filling in the Soil			17.000 M3
Item long text: Construction of compound walls at Tower-1 at HFU/ Tower-1&2 at EM Division /Tower-4 at EM Division : Returning, filling in the Soil, including spreading, leveling, watering and well ramming in layers not exceeding 25cm, etc., complete.					
	Basic Price		INR		
20		Removing the excavated soil material			51.000 M3
Item long text: Construction of compound walls at Tower-1 at HFU/ Tower-1&2 at EM Division /Tower-4 at EM Division : Removing the excavated soil material not exceeding 50 m and depositing where directed at a level not exceeding 1.5 m above the starting point, etc., complete.					
	Basic Price		INR		
21		Providing & fabricating structural steel			150.000 KG
Item long text: Construction of compound walls at Tower-1 at HFU/ Tower-1&2 at EM Division /Tower-4 at EM Division : Providing and fabricating structural steel for framed work as in gratings, doors or gates of angle or other section sliding with and including either hooks and hinges or steel hanging door fittings, also fastening and fixing complete. (HFU)					
	Basic Price		INR		
22		Providing&fabricating steel for gratings			450.000 KG
Item long text: Construction of compound walls at Tower-1 at HFU/ Tower-1&2 at EM Division /Tower-4 at EM Division : Providing and fabricating structural steel for gratings (Framed work such as grills, gratings, etc., with ends of bars shouldered and/or riveted, or forged into spikes; framed guard bars; barred iron doors; ladders; framed and similar work conforming to Fe.290 Gde-E-165, etc., complete.					
	Basic Price		INR		
23		Providing RCC 1:2:4 Concrete			6.000 M3
Item long text: Construction of compound walls at Tower-1 at HFU/ Tower-1&2 at EM Division /Tower-4 at EM Division : Providing RCC 1:2:4 Concrete, using 20mm graded granite aggregate, for Foundation, including footings, foundation beams, plinth beams. bases of columns, etc.					

Bid invitation

Information

Description: EMCP/Compound walls-KGF/

Bid invitation number: 6300037859

Version: 1

Item	Product Price Condition	Description	Vendor product number	Delivery date/ performance period	Quantity
	Basic Price		INR		
24		Providing Cement Concrete 1:2:4			11.000 M3

Item long text:

Construction of compound walls at Tower-1 at HFU/ Tower-1&2 at EM Division /Tower-4 at EM Division :
Providing Cement Concrete 1:2:4, cast in situ, using 20mm graded granite aggregate, for plinth, courses,
copings, parapets and railings, etc., complete.

	Basic Price		INR		
25		Earth work excavation in trenches			25.000 M3

Item long text:

Construction of compound wall at Officers Quarters :
Earth work excavation in trenches in ordinary hard soil not exceeding 1.50 mtrs Wide and deep and getting out,
etc., complete.

	Basic Price		INR		
26		Removing the excavated material			45.000 M3

Item long text:

Construction of compound wall at Officers Quarters :
Removing the excavated material (soil) to a distance not exceeding 500 mtrs, etc., complete.

	Basic Price		INR		
27		Providing PCC 1:4:8			6.000 M3

Item long text:

Construction of compound wall at Officers Quarters :
Providing PCC 1:4:8 using 40mm graded granite aggregate for foundation, etc., complete.

	Basic Price		INR		
28		Demolition of brick/stone masonry			15.000 M3

Item long text:

Construction of compound wall at Officers Quarters :
Demolition of brick/stone masonry built in cement mortar and clearing the debris etc., complete.

	Basic Price		INR		
29		Providing stone masonry wall in CM 1:6			30.000 M3

Item long text:

Construction of compound wall at Officers Quarters :

Bid invitation

Information

Description:EMCP/Compound walls-KGF/

Bid invitation number:6300037859

Version: 1

Item	Product Price Condition	Description	Vendor product number	Delivery date/ performance period	Quantity
		Providing stone masonry wall in CM 1:6 for basement etc., complete.			
	Basic Price		INR		
30		Providing PCC 1:2:4			3.000 M3
Item long text:					
Construction of compound wall at Officers Quarters :					
Providing PCC 1:2:4 using 20mm graded aggregate for plinth and coping etc., complete.					
	Basic Price		INR		
31		Providing burnt brick masonry			22.000 M3
Item long text:					
Construction of compound wall at Officers Quarters :					
Providing burnt brick masonry in cement mortar 1:6 with subclass A brick laid straight including curing, etc., complete.					
	Basic Price		INR		
32		Providing rendering 10mm thick on brick			180.000 M2
Item long text:					
Construction of compound wall at Officers Quarters :					
Providing rendering 10mm thick on brick or concrete surfaces including finishing even and smooth with using extra cement, etc.					
	Basic Price		INR		
33		Providing key pointing in CM 1:4			150.000 M2
Item long text:					
Construction of compound wall at Officers Quarters :					
Providing key pointing in CM 1:4 to stone wall, etc., complete.					
	Basic Price		INR		
34		Fixing only MS angle for fencing work			200.000 KG
Item long text:					
Construction of compound wall at Officers Quarters :					
Fixing only MS angle for fencing work, etc., complete.					
	Basic Price		INR		
35		Preparing the new surfaces of walls			180.000 M2
Item long text:					

Bid invitation

Information

Description:EMCP/Compound walls-KGF/

Bid invitation number:6300037859

Version: 1

Item	Product Price Condition	Description	Vendor product number	Delivery date/ performance period	Quantity
Construction of compound wall at Officers Quarters :					
Preparing the new surfaces of walls and applying two coats of plastic <u>emulsion, etc.,</u> complete.					
	Basic Price		INR		
36		Preparing the old surfaces of steel			20.000 M2
Item long text:					
Construction of compound wall at Officers Quarters :					
Preparing the old surfaces of steel and applying two coats of synthetic <u>enamel paint etc.,</u> complete.					
	Basic Price		INR		
37		Supplying and fixing galvanized wire			600.000 M
Item long text:					
Construction of compound wall at Officers Quarters :					
Supplying and fixing galvanized 2 strand barbed wire etc., complete.					
	Basic Price		INR		