

COMMERCIAL BID**Tender Document No:****Sub : Repair and Renovation of BEML Activity Centre at Chittod Complex Hall, M.P Nagar, Bhopal – 462 011**

Sl. No.	Item Description	Unit	Qty	Unit Rate (Rs)	Amount (Rs)
1	Preparing the surfaces of ceiling and walls by scrapping, sand papering, cleaning dust, dirt etc, and applying 2 coats of premium plastic emulsion paint of approved colour, manufactured by M/s Asian/Berger Paints, conforming to relevant IS over a coat of primer and putty etc., complete all as specified & directed by Officer in charge. Note: The rate quoted is include for a) providing and removal of scaffolding wherever necessary. b) covering doors windows, floors, fittings etc., to protect from splashes.c) Washing floors, cleaning glass, joinery, electric fittings etc., and leaving the premise clean and tidy.	Sft	5934.00		
2	Supplying and fixing powder coated aluminium glazed Partition (Partition/Cabin door/Loft cover sliders) with frame using 1.2mm thick standard sections including with 5.50 mm thick glass and 12mm thick prelaminated board at the bottom including door, rubber beading, gasket, locking handles and fixing in position using all required hardware and aluminium accessories etc., complete all specified and directed by the Officer-in-charge	Sft	1298.00		
3	Dismantling the existing skirting tiles/ tiles /flooring of any description along with the backing coat and carting away the debris outside the premises to place not objected by the local civic authorities including all lead, lift, tolls, labour etc complete all as specified and directed by Officer in charge.	Sft	600.00		
4	Supplying and fixing 50mm diameter CPVC pipeline of first quality, manufactured by M/s.Supreme/ Astral/Ashirvad make conforming to relevant IS including concealing the pipes by cutting chases/grooves in the walls and making good the wall surfaces.The quoted rate shall be deemed to be inclusive of all fittings / fixtures, such as bends, elbows, tees, connectors, caps, plugs, sockets, brass MTA/FTA, adaptor,unions, teflon tape, PVC solvent, all lead, lift, tools, labour etc., complete all as specified and directed by the Officer-in-charge.Note: The rate quoted for the item deemed to include for i)providing and removal of scaffolding wherever necessary ii) wastages.	Rft	160.00		
5	Supplying and fixing new floor mounted/wall mounted Cascade type European type Water Closet with cistern, seat cover and lid, P/S trap, necessary accessories, complete set etc of first quality, Conforming to relevant IS, Manufactured by M/s Parryware/ Hindware/Cera including necessary associated repair works etc complete all as specified and directed by Officer-in-charge.	Nos	2.00		
6	Supplying and fixing new counter sunk hand wash basin of size 550 mm X 490 mm (Approx.) of first quality, conforming to relevant IS, manufactured by M/s. Parryware/Hindware/Cera including 32 mm diameter brass Chromium plated waste coupling Including brackets etc., complete all as specified and directed by Officer-in-Charge.	Nos	2.00		
7	Providing machine polishing to the existing flooring and skirting including removing the stains and finished with wax polish to achieve glossy finish etc., complete all as specified and directed by Officer-in-charge.	Nos	1.00		
8	Supplying and fixing following diameter 6 kg/cm2 pressure SWR PVC sanitary pipes of first quality, conforming to relevant IS, Manufactured by M/s. Supreme/finolex including all bends, collars, tees, reducers, unions, shoe, laid in floors etc, complete all as specified and directed by Engineer -in-charge Nore: The rate quoted for the item deemed ti include for i) Providing and removal of scaffolding wherever necessary ii) wastages.				
a)	110 mm dia	Mtr	6.00		
b)	75 mm dia	Mtr	8		
Grand total inclusive of all taxes and duties				Rs.	0.00