

Corrigendum-2 to tender: 6300038629 dtd 28.11.2023

Tender Term	Point No	FOR	READ
Required Office, Toilet & Security cabin area height	Point no.23 under SCOPE OF WORK	FOR 23. Security Cabins with attached Toilets: 02 Nos., of Security Cabins with attached toilet of size 5.0 Mtr X 5.0 Mtr shall be constructed at both entrance gates.	READ AS: 23. RCC structure for Security Cabins with attached Toilets: 02 Nos., of Security Cabins with attached toilet of size 5.0 Mtr X 5.0 Mtr X 3.0 Mtr Height shall be constructed at both entrance gates.
Sewage treatment plant capacity	Point no.26 under SCOPE OF WORK	FOR 26. Sewage Treatment Plant (STP): Supplying, installation, Testing and Commissioning of Packed unit of required Capacity Sewage Treatment Unit as per norms including required Civil, electrical and mechanical works.	READ AS: 26. Sewage Treatment Plant (STP): Supplying, installation, Testing and Commissioning of Packed unit of 05 KLD Capacity Sewage Treatment Unit as per norms including required Civil, electrical and mechanical works.
	Point no.21 under SCOPE OF WORK	FOR 21. Internal Road & storm water drains, Lorry/Truck Parking, WBM Road - (iii) Providing WBM road: - 6.0 Mtr wide and 900 Mtr Length all-round the compound wall including Preparation, levelling, maintaining required gradient, consolidation of 40mm downgraded granite aggregate WBM / WMM subgrade of required thickness. The road shall be designed for 40 Ton Load.	READ AS: 21. Internal Road & storm water drains, Lorry/Truck Parking, WBM Road - (iii) Providing WBM road: - 6.0 Mtr wide and 900 Mtr Length all-round the compound wall including Preparation, levelling, maintaining required gradient, consolidation of 40mm downgraded granite aggregate WBM / WMM subgrade of required thickness. The road shall be designed for 40 Ton Load. The WMM/WBM roads to have kerb stone on one side. The other side being compound.