

Plant Address
BEML Limited,
Mysore - Engine Division
Belvadi Post
Mysore-570018
Karnataka, India

REQUEST FOR QUOTATION

DATE: 19.11.2022
VENDOR CODE: 694724
CLOSING DT: 01.12.2022
TIN NO: 29040051691

TEL:0821-2402422,
FAX:0821-2402442,0821-2402429,0821-2402434,
EMAIL:bemlz@bsnl.in,bemlmysz@sancharnet.in,beml
mys@sancharnet.in,

Our Ref :MY01/ YMN/1060019570

Dear Sirs,
Please let us have your lowest non negotiable quotation on F.O.R. Destination basis, in duplicate, for supply of following items before 2.00 pm on the Closing Date indicated as above, *addressed to the Senior Manager-Purchase, of the Plant Address mentioned in this Request for Quotation.*

GENERAL TERMS AND CONDITIONS:

1. Term of payment is 100% payment on 30th day for MSEs and for others on 60th day against Work Completion and Certification by User Department. For Bidders not agreeing with the above terms, their quotations will be suitably loaded with applicable cash credit interest while evaluation of bids. In case of early supplies, payment will be made only as per the delivery schedule indicated in the purchase order and in line with the terms of payment.

If firm/firms are quoting payment terms as Advance/Proforma Invoice, firm has to agree to provide Bank Guarantee from a scheduled commercial bank for 110% of their invoice value, only then advance payment will be made. If firm does not agree for the same and only quotes for Advance/Proforma Invoice, such bids are liable for rejection and their offer will not be considered and next lowest technically acceptable offer will be considered. The BG should be valid for a period till the material is received and accepted by BEML.

2. PRICES: Prices are firm till the execution of the Order.

3. DELIVERY TERMS: Delivery as per BEML Schedule.

4. DESPATCH TERMS: F.O.R. BEML MYSORE

5. VALIDITY: 90 Days from the date of opening of the Bid.

6. RISK PURCHASE CLAUSE: BEML Risk Purchase Clause will be applicable.

7. LD CLAUSE: BEML LD CLAUSE will be applicable in case of delay in delivery.

8. TAXES: Firm has to mention SAC Code and applicable GST.

9. The tenders should confirm to BEML specifications, make and conditions in every detail and any tender not conforming to BEML specifications and conditions will be summarily rejected.

Please contact Maintenance Department, Mysore Complex for any technical clarifications.

Phone number: (0821) 2400240/298

E-mail ID: zs@beml.co.in, zsm@beml.co.in

Please contact Materials Department, Mysore Complex for any commercial clarifications.

Phone number: (0821) 2400277

E-mail ID: zmnc@beml.co.in

FOR ADDITIONAL/LESS QUANTITIES (MATERIAL SUPPLY):

Quantities indicated for supply are tentative. Actual quantities may vary as per the site conditions.

In case the quantities required are less than what is indicated in the tender, firm has to supply only those quantities. If firm has supplied more than this quantity, firm will be allowed to take back extra items. However, payment will be made only to the extent of utilized quantity.

In case the quantity required is more than the quantity indicated in the tender, firm has to supply the required quantity at the same agreed price. Purchase Order will be amended accordingly for the purpose of payment.

SL.No.	Our Part Number / Vendor Part Number	QTY	PROC.

SL.No.	Our Part Number / Vendor Part Number	QTY	PROC.
	Description	REQD	UNIT
	Description	REQD	UNIT

SL.No.	Our Part Number / Vendor Part Number Description	QTY REQD	PROC. UNIT
00001	<p>REPAIR-FMS M/C ALU. CHEQUERED PLATFORM</p> <p>Scope of work: (Complete work includes supply of materials and labour- as detailed in Annexure)</p> <p>Removal of existing damaged platforms, dismantling, strengthening and surface preparation for fixing new plywood and Chequered platform. Supply of MS L angle Iron, Aluminium Chequered Plates, Hard wood /plywood, paint, bolt nuts washers, hardware items and any other items as required at site.</p> <p>Firm#s Scope is to supply required materials like MS L Angle Iron, Hard Wood / Plywood aluminium chequered plates, required hardware items like screws / bolt nuts, required painting items like brushes, paint, thinner etc. for 1 coat of red oxide primer, 2 coats of black enamel painting, Complete Labour for metal cutting, gas cutting, welding, grinding, screwing, painting etc. includes Transportation, complete work as required at site / as per operators request and finalised by BEML Engineer In-charge. Any other materials and labour involved, which is not listed above is also in Firm#s Scope, to complete the job as per Operator#s Satisfaction and for intended usefulness.</p> <p>Annexure -1 (PR 1060019570 dt. 20.12.2021) Repair of Existing Aluminium Chequered Plate Platform in FMS Machine Loading / Un-loading Area, by providing 25X25X5mm MS L angle Support, 1inch thick hardwood base support, 4mm thick aluminium chequered plate, hardware items like bolt nut washers, painting for anti rust and black enamel painting. The final dimension & measurement will be as per site condition, as per operators request and finalized by BEML Engineer Incharge. Two Step of Operator#s Platforms were there. First step / bottom platform is of 6 inch ht. approximately and Second step / top platform is of 12 inch ht. approximately. The Approximate dimensions of existing platforms are as under. Bottom Portion : i)2.75 ft X 7.5 ft X 8 nos. = 168 sq.ft ii)2.75 ft X 5.5 ft X 2 nos. = 30 sq. ft. (total 198 sq. ft for 10 box) Top Portion : iii)5.5 ft X 6 ft X 14 nos. = 462 sq.ft iv)5.5 ft X 13.5 ft X 1 no. = 75 sq.ft v)5.5 ft X 3.5 ft X 1 no. = 20 sq.ft vi)5 ft X 9ft X 1 no. = 45 sq. ft. (total 602 sq. ft for 17 box) Approx. Bill of Materials is estimated as under : 1)Aluminium chequered plate 4mm thick # size for both First Step & Second Step platforms ---- Total 800 sq.ft X 1.15 (adding 15% wastage) = 920 SFT OR say 44 nos. of</p>	1.000	Activ.unit

SL.No.	Our Part Number / Vendor Part Number Description	QTY REQD	PROC. UNIT
	<p>sheet of size 4mm x 3# x 7# size. (924 sq.ft)</p> <p>2)Hard plywood 1# thick # size for both First Step & Second Step Platoforms ---- Total 800 sq. ft X 1.15 (adding 15% wastage) = 920 SFT OR say 44 nos. of Hard wood /Neem Playwood sheet of size 1# x 3# x 7# size (924 sq. ft)</p> <p>3)MS Material # 25 x 25 x 5 mm angle # size for both First Step & Second Step Platforms -- 60 length (1 length = 20 ft. # for First Step # 10 box X 2 length for each = 20 length, for Second Step # 17 box X 2 lenth for each = 34 length, total 54 length. Add 10% wastage -- Aprox. 60 length OR say 25x25x5mm x 20ft long # 60 length required.</p> <p>vi)Miscellaneous hardware items like Screws / Rivets / Bolt Nuts Washers etc. and painting items for 1 coat of Red oxide primer and 2 coats of black enamel painting.</p> <p>Revised Estimation: (considering 8 box for bottom platform & 13 boxes for top platform)</p> <p>Item no. Item Description Qty. in length / nos. / sq. ft Material Cost Labour Charges</p> <p>1 MS Material 25 x 25 x 5 mm angle 44 length</p> <p>2 1# thick hard plywood 656 sq. ft</p> <p>3 4mm thick aluminium chequered plate 656 sq. ft</p> <p>4 Miscellaneous Paint & hardware items like bolt nut rivet screw etc. and paint material for 1coat of Red oxide primer and 2 coats of Black enamel painting. 01 lot</p> <p>4 Removal & Dismantling of existing damaged platforms & strengthening, surface preparation for plywood & Alu. Chequered platform 01 job</p> <p>5 Complete Labour cutting, welding, painting etc. as required. 01 job</p> <p>G. Total</p> <p>Firm#s Scope is to supply required materials like MS L Angle Iron, Hard Wood / Plywood aluminium chequered plates, required hardware items like screws / bolt nuts, required painting items like brushes, paint, thinner etc. for 1 coat of red oxide primer, 2 coats of black enamel painting, Complete Labour for metal cutting, gas cutting, welding, grinding, screwing, painting etc. includes Transportation, complete work as required at site / as per operators request and finalised by BEML Engineer In-charge. Any other materials and labour involved, which is not listed above is also in Firm#s Scope, to complete the job as per Operator#s Satisfaction and for intended usefulness</p> <p style="text-align: right;">Qty. unit Deliv.date 1.000 Activ.unit 31.12.2022</p>		

SL.No.	Our Part Number / Vendor Part Number Description	QTY REQD	PROC. UNIT
The item covers the following services:			
01	Supply - MS Angle 25X25X3 mm-20' length	44	NO
02	Supply - 1" thick hard wood/ plywood	656	FT2
03	Supply - 4mm thick Alu. chequered plate	656	FT2
04	Supply - Miscallaneous paint, hardwares	1	LOT
05	Labour-dismantling existing platforms	1	JOB
06	Labour-cutting, welding, painting etc.	1	JOB

Thanking you
Yours faithfully
For BEML Limited.,

Authorized Signatory

Refer Annexure for TERMS and CONDITIONS